



**Standing Committee on Concrete Technology
Annual Concrete Seminar 2019**

**Harbour Area Treatment Scheme Stage 2A
Long-Distance Concrete Placing**

KY Chan (AECOM Asia)

Nick Gibbs (Gammon Construction)



Outline

- 1st part – by Mr. K Y Chan
 - Project Introduction & Background
 - Consideration of choosing long-distance concrete pumping


- 2nd part – by Mr. Nick Gibbs on
 - Project delivery including logistics, trial pours, concrete distribution system, high performance concrete mix design etc.



HATS Stage 2A Project Background




Harbour Area Treatment Scheme (HATS) Stage 2A Sewage Conveyance System (SCS)







Harbour Area Treatment Scheme – Stages 1 and 2A






HATS Stage 2A Sewage Conveyance System - Alignment






Legend:
Soil Layer
Bedrock



Typical Cross Section





Tunnel L
(3000 diameter)

Tunnel K
(1200x2400 + 1100x2000)




Access constraints

- Access via deep shafts (>150m)
- Small diameter (~4m)
- One way traffic
- Passing bays at ~800 to 1200m






Concrete Delivery Arrangement



Formwork Concreting Operation



Vault Formwork




Scissor pipes



Formwork Carrier with Invert Formwork

Delivery by Train Remixer



Train speed	=	6km/hr
Average Travelling Time (round trip)	=	10min
Average Time to discharge	=	15min
Capacity of each train mixer	=	7m ³
Concreting rate	=	16.8m ³ /hr




Means to enhance concreting rate

Method	Concerns
Increase train speed	Risk of de-railing, safety concerns
Twin track	Time and cost for increased excavation and backfilling
Closer passing bays	Time and cost for increased excavation and backfilling

Delivery by LDPC (Long Distance Pumping of Concrete)



Concrete Delivery by LDPC



Concrete Pump at Formwork



Concrete Pump at Shaft Bottom



Discharge Rate of LDPC

Pipe diameter = 150mm

Area = 0.018m²

velocity = 0.5m/sec

Pumping rate = 31.8m³/hr

(>16.8m³/hr by train remixer)

Time to travel 1 km = 33min



Compare LDPC with Train Remixer

Advantages	LDPC	Train Remixer
Higher concrete delivery rate	~32m ³ /hr	~17m ³ /h
Occupy less space	150mm diameter pipe	Train remixers
Steady supply of concrete at face	Continuous	Break after discharge each train
Potential Problems / Limitations		
Longer travelling time	0.5 m/sec = 1.8 km/hr	6 km/hr
Risk of pipe blockage	Yes	No
Limited distance	Up to 1.2 km in HATS experience	Up to 4.5 km in HATS




Specification and Design Mix Requirements



Category	GS (2006) - Marine Concrete (Grade 45/20D)	DSD HATS2A (Plain marine concrete Grade 45/20D)
Concrete mix		
	(i) Min grade 45 MPa (ii) Max 0.38 w/c ration (iii) 375-450 kg/m ³ cementitious materials with 25-40% PFA and 5-10% condensed silica fume	
	PC, SRPC, PFAC, PBFC, CSF	Sulphate Resisting Portland Cement
Concrete Performance		
Temperature	Placing temp < 30°C	(i) Placing temp < 32°C (ii) Peak ≤ 70°C (iii) Max difference ≤ 20°C
Strength	same as normal concrete	Any consecutive 40 results of 28d cube strength: - <u>Coefficient of variation ≤ 8%</u> - <u>Average strength ≥ Grade + 2x standard deviation</u>
Durability	not specified	- <u>28d AASHTO chloride diffusion (6 hour hour test) ≤ 1,000 coulombs</u> - <u>28d water sorptivity ≤ 0.07 mm/min^{0.5}</u>



Lining Logistics






Lining Logistics

Activity	Duration	1 hour		2 hours		3 hours		4 hours		5 hours		6 hours	
		30 mins	30 mins	30 mins	30 mins	30 mins	30 mins	30 mins	30 mins	30 mins	30 mins	30 mins	30 mins
Mixing at batching plant and transport to site	1 hr	█	█										
Queuing at site	0.25 hrs			█									
Vertical discharge via slickline	0.25 hrs			█									
Convey to face by train mixer / pump	0.5 hrs				█								
Placed in final position (earliest / latest)	0.5 - 2.5 hrs					█	█	█	█	█			
Contingency	1.5 hrs									█	█	█	

Slump $\geq 200\text{mm}$ at 6 hours after mixing with water
 Early strength $\geq 1\text{ Mpa}$ at 6 hours for Tunnels J and K
 Early strength $\geq 3\text{ Mpa}$ at 8 hours for Tunnel L

- Tunnels J and K shutter length 15m
- Tunnel L shutter length 60m
- Careful balance between appropriate admixture dosing and operational control onsite (truck queuing, pump line static times)

Concrete Design Mix



- Particle packing optimised through replacement of cementitious material with inert fines
- Water also reduced and superplasticisers added to maintain workability
- Result is good workability, high performance concrete that satisfies durability requirements



Concrete Design Mix

ID	Type	Designation	Workability	w/cm	CSF content	PFA content	CM (kg/m3)	Fine (kg/m3)	Coarse (kg/m3)	Admixtures (L/m3)
1	Self-compacting	15/10D	680mm SF	0.42	0%	58%	440	820	830	6
2		45/10D	700mm SF	0.37	6%	31%	435	780	950	8
3	High-performance	45/20D	200mm slump	0.38	6%	31%	435	730	1000	11
4		45/20D		0.37	6%	31%	435	750	1000	11
5		60/20D		0.35	6%	30%	450	765	1000	8
6		60/20D		0.35	6%	30%	450	765	1000	8
7		80/20D		0.31	5%	25%	450	770	1020	11
8	Very early strength	45/20D	225mm slump	0.38	6%	31%	435	780	950	17
9		60/20D		0.34	6%	28%	450	810	940	17

CSF	Condenses Silica Fume	10 microns
PFA	Pulverised Fly Ash	50-100 microns
CM	Cementitious Materials	100-150 microns
	Fine Aggregates	~0.5-2mm
	Coarse Aggregates	~20mm

Mix 1 - 2 used for shaft backfilling where needed

Mix 3 - 7 used for tunnel lining

Mix 8 - 9 used as contingency

Thermal shrinkage control for 60m length, +500m³ placement

Controlled by:

- Low cementitious material content to reduce thermal shrinkage effects including cracking
- Early age strength targeted to resist shrinkage in plain concrete lining



Formwork Systems and Logistics


Trial Pour and Design Mix Review



- Extensive honeycombing in early trials due to high viscosity of concrete and cement/ admixture reaction
- Design mix adjusted to include additional inert material and use of superplasticisers to maintain workability



Tunnel L – Telescopic Formwork System



- Formwork systems hand made in Italy
- Fabricator inspection and pre-assembly
- Repeat pre-assembly in HK before lowering to tunnel for lining construction



Tunnels J and K – Invert and Vault Shutters






Concrete Distribution System





Tunnel L - Telescopic Formwork System





Tunnel L – Telescopic Formwork System





Tunnels J and K – Invert and Vault Shutters





When things go wrong...







Tunnel L - Lining Production

Month	Cycles	Start Chainage	Finish Chainage	Lining Completed (m/ month)
Dec-14	10	8	438	430
Jan-15	16	438	1+350	912
Feb-15	16	1+350	2+319	969
Mar-15	17	2+319	3+288	969
Apr-15	18	3+288	4+222	934
May-15	6	4+222	4+478	256
Total	83			4,470

HATS2A - Tunnel L Cycle Time



HATS2A - Tunnel L Concrete Placing Rate



Conclusions



- Stringent strength and durability requirements achieved through innovative design mix with consideration to long distance placing method and QA/QC processes
- High production and reduced plant for safer delivery
- Concrete design, control on manufacturing and quality processes important to delivery

Conclusions



- 2011 cross harbour swim resumed at Lei Yue Mun, first time since 1978!
- 2017 sees return to centre of Victoria Harbour for first time in nearly 40 years



Thank you