





3
≺.
_

Aganda	ARUP
Agenda	
Removal of Formwork	5
What is Maturity Method	10
Maturity Functions	15
Type of Sensors	22
Formwork Striking	26
Teperature Match Curing	28
Site Trial in HK	31
Applications	37
Summary	39

Removal of Formwork

Removal of formwork and falsework HKCoP-cl 10.3.8.2 ARUP

Formwork supporting cast insitu concrete in flexure may normally be struck when the strength of the concrete in the element is 10 N/mm^2 or twice the stress to which it will be subjected,

Elements	Time to strike formwork
vertical formwork for sides of beams, columns, walls and similar locations	12 hrs
soffit formwork of slabs with props left in;	4 days
soffit formwork of beams with props left in;	7 days
props for slabs	10 days
props to beams	14 days
props to cantilevers	14 days

101347 α	ACI 2-2	20					
GUIDE TO FORMWC Table 5.72.3—Guidance for stripping time wher stripping strength required	DRK FOR CONCRETE (ACI 374R-14) n contract documents do not sj	17 pecify stripping time or	Table 5.1—F	Recomm	endations f	or slabs	,
Structural element supported	Structural live load not greater than structural dead load	Structural live load greater than structural dead load	Silvar maile,	una oon	omano		
Walls	12 hours	12 hours		Num	ber of test	No.	
Columns	12 hours	12 hours		locatio	ns provided	Number of	locations to tes
Sides of beams and girder Pan joist forms? 30 in. (760 mm) wide or less Over 10 in. (760 mm) wide	3 days	3 days	Test method	First 75 m ³ (100 yd ³)	Each additional 15 m ³ (20 yd ³)	First 75 m ³ (100 yd ³)	Each additiona 15 m ³ (20 yd ³
Arch centers	14 days	7 days	Rehound				
Joist, beam or girder soffits Under 10 ft (3 m) clear span between structural supports 10 to 20 ft (3 to 6 m) clear span between structural supports	7 days ¹ 14 days ¹	4 days 7 days	number	20	2	10	1
Over 20 ft (6 m) clear span between structural supports	21 days ¹	14 days	penetration	8	1	6	1
Under 10 ft (3 m) clear span between structural supports 10 to 20 ft (3 to 6 m) clear span between structural supports Over 20 ft (6 m) clear span between structural supports	4 days ¹ 7 days ¹ 10 days ²	3 days 4 days 7 days	Pin penetration	15	2	10	1
Two-way slab systems ¹	Removal times are contingent on place	ment of reshores where required. Reshores	Pullout	15	2	10	1
should be placed as soon as practicable after attripting operations are complete but not later than the end of the working day in which stripting excess. Where reshores are required to implement early stripting while minimizing age or energy that the for distribution of momentum of comparison target stripting while minimizing age or energy that the stripting of the stripting and the stripting while minimizing age or energy that the for distribution of momentum of comparison target stripting while minimizing age or energy that the for distribution of momentum of comparison target stripting while minimizing age or energy that the stripting of the stripting while minimizing age of the stripting while minimizin		Ultrasonic pulse velocity	15	2	10	1	
	spacing of such reshores should be desig	and by the formwork engineer/contractor	Break-off	10	2	8	1
Post tensioned slab system ¹	As soon as post-tensioning operations	have been completed and approved	Maturity	5	2	5	1
Where such forms also support formwork for slab or beam soffers, the removal 'Of the type that can be removed without disturbing forming or shoring. Where forms can be removed without disturbing shores, use half of values sho Refer to Section 5 & for needs to confision affection the number of homes to rem	times of the latter should govern.		Cast-in-place cylinder [†]	5	1	5	1
A	CI 347		*Core walls that typ a building and form *For slabs only.	ncally surrour the structural	id elevator shafts ar backbone of the bu	e usually loc: iilding.	ated at the center of

《結構混凝	土施二	工規範	- TaiWan
4.7.6使用第1型水泥且不掺卜作崩材料= 外不得少於表4.7.1之規定。 +4.7	发其他掺料之混凝土 1 是小任好時間	,其拆模時間除依第4.7	^{×规定} 經驗值 - 跨度小於等於8米的梁板底模及小於等 於2米跨的懸樑拆模時間為:
衣4.7. 楼住 名稱	1 取少拆供时间 品小拆	超時間	
(時)「石田 村、焼、及湿之不供も推測規	12	小時	
警向 栅版不影響支撑之般模"	12	1.41	1) 日半均温度為5度時,拆模時間為20大,
75 cm以下	3	天	2) 日平均溫度為10度時,拆模時間為14天;
大於75 cm	4 天		3) 日平均溫度為15度時,拆模時間為11天;
:	活载重不大於靜載重	活载重大於静载重	
單向版			
淨跨距小於3 m	4 天	3 天	5) 日半均温度為25度時,
滲跨距3 m至6 m	7 天	4 天	平均溫度為30度時,拆模時間為6天。
淨跨距大於6m	10 天	7 天	
拱模	14 天	7 天	
柵肋梁、小梁及大梁底模			亚古美雄岛边古美雄
淨跨距小於3 m	7 天	4 天	邓汨莨磑央汉汨莨磑,
淨跨距3 m至6 m	14 天	7天	ᇴᆂᄺᇧᄮᅖᅆ
净珍距大於6m	21 天	14 天	义有凹分別?
受问版 从上 环 上 K 多 体	依據第4.8	5即之規定	
皮 拉 損 刀 放 糸 筑	全部預力方	也加元成後	Is there any difference in
			time if we have curing?

ARUP Current Practice to Obtain the in-situ Strength

Break Tests

- Making cubes to be tested
- Curing cubes in water (usually 25° C)
- Test cubes at or day *X*, ..., 7 and 14 days

Are you sure the in-situ concrete are also 25° C?

What happen if the temperature is

> 25° C or < 25° C ?













Maturity Functions



Nurse-Saul Method

It is knowns as the **Temperature Time Factor (TTF)** and commonly used in maturity method. It assumes that the rate of strength development is a linear function of temperature as

$$M(t) = \sum (T_a - T_0) \Delta t$$

Where:

M(t) = the temperature-time factor at age t, degree-days or degree-hours, Δt = a time interval, days or hours, T_a = average concrete temperature during time interval, Δt , °C, and

 $T_0 =$ datum temperature, °C.

17







Calibration Casting/Curing/Testong







Casting specimens with concrete mix utilized for calibration

Curing at 3 different temperatures as required to extract maturity model parameters

Determination of compressive strengths at pre-established times and for each curing temperature

21

process











Removal of formwork and falsework HKCoP-cl 10.3.8.2 ARUP Formwork supporting cast insitu concrete in flexure may normally be struck when the strength of the concrete in the element is 10 N/mm² or twice the stress to which it will be subjected, **Elements** Time to strike formwork vertical formwork for sides of beams, columns, walls and similar locations 12 hrs soffit formwork of slabs 那有養護與沒有養護, 4 days soffit formwork of beam 又有何分別? 7 days Is there any difference in props for slabs 10 days time if we have curing? props to beams 14 days props to cantilevers 14 days 27







ARUP

Site Trial in HK

31

21

Case Studies/ HK Trials

CIC provided the Arup team with access to the following on-going construction projects.

Projects	Structural Element	Concrete Strength	Cement replacement
HyD Central Kowloon Route (Trial no. 1 and 4)	Roof slab	45/20D	35% Fly ash
DSD Shek Wu Hui Effluent (Trial no. 2)	Slab and Beam	50/20D	25% Fly ash
ArchSD Kai Tak Rain Garden (Trial no. 3)	Slab	40/20D	No. CEM 1 only!
CEDD Kwu Tung North (Trial no. 5)	Retaining Wall	30/20D	25% Fly ash

Case Studies/ HK Trials

SITE TRIAL NO. 5: CEDD Kwu Tung North, Retaining Wall

Key Activity	Date/ Period
Sensor Installation	21 December 2021
Site Trial	23 Dec 2021 – 20 Jan 2022

Sensor System	Data Logger	Temperature Sensor
Command Center	1 No.	4x Surf. 🔵
Converge	4 No.	4x Surf. 🔘
Lumicon	4 No.	4x Surf. 🔾
SmartRock	N/A (fully wireless)	4x Surf. 🗢











ARUP

Applications of Maturity Method

37

Applications

Construction Type	Applications
Buildings	 stripping forms of vertical elements removing falsework in 1-way/2-way slabs once required strength is obtained
Infrastructures	 stripping forms and removing falsework safely in cast-in-situ tunnel liners apply post-tension in bridge decks or beams when required strength is achieved determining the actual temperature differential allowed in order to prevent cracking in mass concrete
Precast yards	 early stressing of tendons in pre- or post-tensioned precast elements early lifting & staking of tunnel segments or other precast products
Pavements	 appropriate time for opening a pavement to traffic (construction or public) for sawing joints ceasing special concreting
Others	 estimating modulus of elasticity at very early ages in deformation sensitive members correct estimate of strength properties to avoid damages during the lifting process of tilt-up members estimate strength in sprayed concrete sections

Summary

Ability to predict the strength of portland cement concrete and fly ash concrete with good accuracy and applicable to HK. The deviation between maturity estimate and real in-situ strength (temperature matched curing) is within 10% A correction factor system that avoids over/under estimation and keeps the maturity model in check. The method demonstrated reduction in formwork removal time of at least 60% (60 ~ 90%) from code specified striking times e.g. potential to reduce cycle times from as low as 2.8 days to as much as 13 days Maturity method now accepted by BD - incorporated in BD Circular Letter – Amendments to the COP SUC 2013 clause 11.7.5.4 and Table 11.2

Further Opportunities

- 1. Promote characterization of new concrete mixes, particularly those involving high replacement levels (low carbon concretes)
- It is still required to analyze the effects of varying cement contents, w/c ratio or level of fly ash or GBBS replacements
- 3. Possibility to drive carbon reduction the maturity method offers the potential to explore reduction in the binder intensity of the concretes





